FOR MYSORE STATE

P.W (1953) Department.

MS SERIES.

G.O. NO. 3013

3013

Dated 16-7-53.

[Despatch Abstract.]

Irrigation - Concrete and Physics and Soil mechanics Laboratories, Chepauk, Madras Tests Conducted on behalf other departments of Madras Govts, other Govts and Private persons and bodies - Levy of Charges - Rates fixed.

Public Co.

Subject - Grant-in-aid - Physics and Physical Chemistry Laboratories, Guindy, Madras - Rules conducted on behalf of other Departments of Madras Government other Governments and Private persons and bodies - Levy of charges - Issue of Memo.

ROLLING ORDER No. 2 of 1953.

G.O.Ms.No.2013 Dated the 16th July 1953.
Read the following:

G.O.Ms.No.1728 ... dated 6-5-1948.
G.O.Ms.No.711 ... dated 2-3-1949.
G.O.Ms.No.1271 ... dated 10-4-1950.

From the Chief Engineer (Irrl. Design-I) Lr.No.1859/51-A.5 dated 4-6-1953.

ORDER:

The Government direct that in respect of tests conducted in the Concrete Laboratory and in the Physics and Soil Mechanics Laboratory, Guindy, Madras, on behalf of other Departments of the Madras Government, other Governments or private persons and bodies, fixed charges as laid down in the annexure to this order be levied, instead of the actual expenditure incurred in connection with the tests. The rates fixed in the annexure to G.O.Ms.No.1728 P.W. dated 6-5-1948 as modified in G.O.Ms.No.417 P.W. dated 10-2-1949.

The Chief Engineer (Irrl. Design-I) is requested to arrange, in consultation with the Accountant General, Madras 7 to watch the collection of the charges.

(By order of the Governor of Madras.)

[illegible]

To
The Chief Engineer (Irrl. Design-I),
Madras.
The Accountant General, Madras 7.
The Director of Industries, Madras.
The Director of Industries and Commerce, Madras.
The Director of Agriculture, Madras.
The Director of Public Health, Madras.
The Director of Veterinary Services, Madras.
The Director of Fisheries, Madras.
The Director of Stationery and Printing, Madras.
The Director of Information and Publicity, Madras.
The Director of Geology, Madras.
The Director of Mines, Madras.
The Director of Geology and Mines, Madras.
The Director of Statistics, Madras.
The Director of Town Planning, Madras.
The Director of Fisheries

Annexure.

Statement showing charges to be levied in respect of tests conducted on behalf of other departments of Government, other Governments etc., in the Concrete Laboratory and the Physics and Soil Mechanics, Laboratory, Chepauk, Madras.

CONCRETE LABORATORY.

Cement testing:

Complete test of a sample of cement (Consistency, setting time, soundness and strength)	Rs.20-0-0

Aggregate testing:

Complete test of a sample of a coarse aggregate (physical properties, soundness, petrographic analysis and strength in concrete)	Rs.40-0-0
Complete test of sample sand (physical properties, mechanical analysis soundness petrographic analysis and strength)	Rs.25-0-0

Strength tests:

Compressive strength of 4 in. cubes; per cube	Rs. 0-6-0
-do- 6" cubes -do-	Rs. 0-8-0
over 6" and upto 12" cube.	Re.1-0-0

Tensile strength including percent elongation and per cent reduction in cross section, but excluding determination of value of 'E'.

For rods upto 1" dr. or 1" side each rod	Rs. 1-8-0
-do- 1" and 1¼"	" 2-0-0
-do- above 1¼" dr. or side.	" 2-8-0
Extra charges for determination of 'E' per rod.	" 2-0-0

PHYSICS AND SOIL MECHANICS LABORATORY.

For routine tests only - per sample -- (i.e. Mechanical Analysis, Atterberg Limits, F.M.E., Shrinkage factors and compaction characteristics or any part of these tests)	Rs.16-0-0
For direct shear test - per sample.	Rs. 5-0-0
For permeability test - per sample.	" 3-0-0
For triaxial Shear test per sample	" 8-0-0
For any additional tests per sample	" 6-0-0

****

/True copy/

G. Santanarayanan

Superintendent.

gr/
24/7